BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/06/2020-21 Dated: 14-09-2020

APPROVED TENDER SCHEDULE –'B'

Item 8

Name of Work :-Maintenance of BBMP office Building in chowdeshwri ward no -02 of yelahanka Sub division

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri SHIVAKUMAR N	
				Rate	Rate in Words
1	Supplying steel Almirah with shelves & locker 6.6feet 18/20 gaugeof size 78" x 36"x 19" etc. including of all taxes as per approved by engineer in charge (Data rate) complete as per specifications.Specification .and directoin of site engineer in incharge	No	6.00	12617.61	Twelve Thousand Six Hundred Seventeen Paise SixtyOne Only
2	Providing executive revolving chairs with full high back with head rest etc., complete inclusive of all taxes as per direction of engineer in charge (Data rate) complete as per specifications.Specification .and directoin of site engineer in incharge	No	4.00	8308.89	Eight Thousand Three Hundred Eight Paise EightyNine Only
3	Laser Printer With Auto Duplex Printng of Make canon /Brother/HP Data Rate complete as per specifications.Specification .and directoin of site engineer in incharge	No	1.00	20990.00	Twenty Thousand Nine Hundred Ninety Only
4	Laser Printer with print /Scan/Copy Options with Auto Duplex of Matte canon /HP Data Rate complete as per specifications.Specification .and directoin of site engineer in incharge	No	2.00	36732.50	ThirtySix Thousand Seven Hundred ThirtyTwo Paise Fifty Only
5	HP 200 Pro G4 22 All in one 9th Generation Intel Core™ i5 processor Data Rate complete as per specifications.Specification .and directoin of site engineer in incharge	No	1.00	78712.50	SeventyEight Thousand Seven Hundred Twelve Paise Fifty Only
6	Providing Industrial Mops With Bucket (Market Rate) complete as per Specification .and directoin of site engineer in incharge	No	4.00	10495.00	Ten Thousand Four Hundred NinetyFive Only

	dustrial Mop Sticks For Cleaning/ wiping of Floors and maintenance. (Market Rate) complete as per specifications and directoin of site engineer in incharge	No	10.00	3148.50	Three Thousand One Hundred FourtyEight Paise Fifty Only
8	Providing Hand Wash Soap Solution each container of 500 ml (Market Rate) complete as per Specification .and directoin of site engineer in incharge	No	15.00	524.75	Five Hundred TwentyFour Paise SeventyFive Only
9	Providing Wall Mounted Hand wash soap Dispensor (Market Rate) complete as per Specification .and directoin of site engineer in incharge	No	8.00	3148.50	Three Thousand One Hundred FourtyEight Paise Fifty Only
10	Providing Phenyl For Cleaning and Maintainance, Each can of 5Liters (Market Rate) complete as per Specification .and directoin of site engineer in incharge	No	15.00	839.60	Eight Hundred ThirtyNine Paise Sixty Only
11	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per Specification .and directoin of site engineer in incharge	Sqm	904.96	102.01	One Hundred Two Paise One Only
12	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, complete as per Specification .and directoin of site engineer in incharge	Sqm	182.52	385.38	Three Hundred EightyFive Paise ThirtyEight Only
13	Providing external walls with texture finish using approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental complete as per Specification .and directoin of site engineer in incharge First Floor	Sqm	186.75	394.44	Three Hundred NinetyFour Paise FourtyFour Only

	roviding external walls with texture finish u g approved brand paint, applied uniformly in three coats over one coat of primer including cost of all materials, machineries, labour, transportation, loading and unloading, all lead and lift and all other incidental charges including scaffolding and removing stains, complete as per specifications.Specification .and directoin of site engineer in incharge Second Floor	Sqm	200.31	403.51	Four Hundred Three Paise FiftyOne Only
15	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testing complete as per specifications.Specification .and directoin of site engineer in incharge For Rain water pipe. 110mm Dia	m	10.00	491.92	Four Hundred NinetyOne Paise NinetyTwo Only
16	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials,labour charges, HOM of acquirements and testingcomplete as per specifications.Specification .and directoin of site engineer in incharge 160mm Dia	m	8.00	966.84	Nine Hundred SixtySix Paise EightyFour Only
17	Providing and placing on terrace, polyethylene water storage tanks with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 2000 Litre capacity) complete as per specifications.Specification .and directoin of site engineer in incharge	Each	2.00	15478.53	Fifteen Thousand Four Hundred SeventyEight Paise FiftyThree Only

	roviding and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,)complete as per Specification .and directoin of site engineer in incharge 20mm nominal OD pipes	m	55.00	266.36	Two Hundred SixtySix Paise ThirtySix Only
19	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.,)complete as per specifications.Specification .and directoin of site engineer in incharge 25mm nominal OD pipes	m	40.00	332.10	Three Hundred ThirtyTwo Paise Ten Only
20	Supplying of .....feet - PVC Batten with integrated LED tube .....W with high quality diffuser with Life of 25000 burning hours & 70% lumen maintenance with CRI > 80. Power Input: 220-240V @ 50/60Hz & Power factor >0.9 along with CE approved. 2 years Warranty against any manufacturing defect working under standard electrical condition. LED light fighting 1 x4'- 20/22 w complete as per Specification .and directoin of site engineer in incharge	Each	50.00	393.56	Three Hundred NinetyThree Paise FiftySix Only

	upplying & fixing retrofit type -PL- LED Lamp .....W LED linear source with CCT 6500 degree K, CRI> 70%. efficacy >80 lumen per watt, life> 25000 burning hours and Compliance to IS 10322/IEC 60598, LM 79 & LM 80. The LED are driven by HF electronic driver integrated in the system, with PF > 0.95, power loss should < 5% of lamp wattage., short circuit & open circuit protection to be integrated in the circuit, THD less than 20%, Life as per LM 79. The operating input voltage should be between 130 to 275 volts. Tested by NABL/CPRI accredited laboratory with 2 years Warranty against any manufacturing defect working under standard electrical condition.8-9 Watts complete as per Specification .and directoin of site engineer in incharge 8-9 Watts	Each	15.00	367.33	Three Hundred SixtySeven Paise ThirtyThree Only
22	Supplying & fixing retrofit type -PL- LED Lamp .....W LED linear source with CCT 6500 degree K, CRI> 70%. efficacy >80 lumen per watt, life> 25000 burning hours and Compliance to IS 10322/IEC 60598, LM 79 & LM 80. The LED are driven by HF electronic driver integrated in the system, with PF > 0.95, power loss should < 5% of lamp wattage., short circuit & open circuit protection to be integrated in the circuit, THD less than 20%, Life as per LM 79. The operating input voltage should be between 130 to 275 volts. Tested by NABL/CPRI accredited laboratory with 2 years Warranty against any manufacturing defect working under standard electrical condition.8-9 Watts complete as per Specification .and directoin of site engineer in incharge 18-20 Watts	Each	20.00	446.04	Four Hundred FourtySix Paise Four Only

	Supplying capacitor type ceiling fan complete with down rod blades shackle, canopies etc, for operation on 230 volts, 50 cycles. single phase AC supply conforming to ISS-374-1979 and with double ball bearing system complete as per Specification .and directoin of site engineer in incharge	Each	30.00	2193.46	Two Thousand One Hundred NinetyThree Paise FourtySix Only
24	Supply Exhaust fan if 1440 RPM of (12") size with dracket blades complete for light duty suitable to -oerate on 230V 50Hz, supply complete as per Specification .and directoin of site engineer in incharge	Each	7.00	1259.40	One Thousand Two Hundred FiftyNine Paise Fourty Only
25	Supplying, erecting, testing & commissioning of ON-LINE UPS system suitable for operation on 230V, 50Hz, A/C supply, with isolation transformer all accessories complete and Excluding batteries and wiring complete. 3 KVA ON LINE UPS complete as per Specification .and directoin of site engineer in incharge	Each	1.00	44582.76	FourtyFour Thousand Five Hundred EightyTwo Paise SeventySix Only
26	Supplying, installation, testing & commissioning of 12V DC, AH batteries in poly propylene container for U.P.S. Sealed maintenance free batteries. 75 / 80 AH capacity complete as per Specification .and directoin of site engineer in incharge	Each	4.00	9130.65	Nine Thousand One Hundred Thirty Paise SixtyFive Only

Signature of the Contractor

Executive Engineer
Yelahanka Division,
BBMP, Bengaluru-64

Executive Engineer
Bruhat Bengaluru Mahanagara Palike
Yelahanka, Division